Statement showing the approximate quantities of work for constructing a Sub-Station at the junction of Subedar Chattram and Race Course Road.

No.	Items of work	Rate Unit	Quantities, approximate
1	Earthwork, excavation and filling in basement	C. yd.	831
2	Concrete foundation	C. ft.	6,167
3	Stone in mortar, foundation and basement	"	10,111
4	Stone in mortar, superstructure	"	27,104
5	Stone slabs, 6" thick, exposed parts dressed	S. ft.	1,808
6	Cut-stone arch work	C. ft.	876
7	Quoire stones, 1" draft chiselling	"	708
8	Nicely dressed stone cornice, 6" deep	R. ft.	418
9	Brick cornice, 12" projection	"	385
10	Ornamental parapet wall	"	42
11	Cut-stone pillars with pedestals	No.	10
12	Ornamentation to basement windows	"	4
13	Cement pointing	Sqr.	353 78
14	Mangalore tile flooring on 3" concrete	"	48·55
15	Madras terrace roofing	"	1·69
16	Cement concrete arches on I beams and Mangalore tile flooring	"	42·73
17	Teakwood flooring, 1½" tongued and grooved	"	9·63
18	Mangalore tile roofing on galvanized corrugated iron sheeting	"	77·10
19	Ridge tiles set in mortar	R. ft.	202
20	Zinc sheeting to valleys	"	116
21	Ornamental eave guttering fixed, complete	"	246
22	Cast iron pillars, 11 ft. long	No.	8
23	W. I. trusses, 36 and 31 ft. clear span	"	14
24	Hoisting charges, etc., for the above trusses	"	14
25	W. I. work fixed, complete	Cwt.	262·37
26	Bolts, and nuts, etc.	"	5
27	W. I. pipe railings to galleries	R. ft.	225
28	Teakwood work with wood oiling	C. ft.	882·93
29	Teakwood panelled and glazed doors	S. ft.	479
30	Teakwood glazed windows	"	1,432
31	T. W. circular and semi-circular windows	"	290
32	Painting with 3 coats of silicate paint	Sqr.	50·56
33	Pressed brick in cement	C. ft.	183
34	Cement concrete slabs, 2" thick	"	210
35	Wire gauge shutters	S. ft.	807
36	Fifty lbs. rail to travelling crane	R. ft.	200
37	Galvanized iron rain water down pipes, 4½" diameter	"	700

S. G. FORBES,
Chief Electrical Engineer to the Government of Mysore.

Notice, Camp Hassan, dated 10—14*th February* 1918.

It is hereby notified, for the information of the officers concerned, that the Departmental Examination for Assistant and Sub-Assistant Engineers, prescribed in Government Order No. 311-5—P. W. 1859-63, dated the 17th February 1917, will be held in the Chief Engineer's Office at Bangalore, on Monday the 5th August 1918.

2. Candidates must send in their applications through the proper channel in the form prescribed with the necessary certificates to the undersigned on or before the 20th June 1918.

S. CADAMBI,
Chief Engineer of Mysore.

WATER-SUPPLY DIVISION.

Abstract Notification, dated 4th February 1918.

The attention of the public is drawn to the Notifications calling for tenders for the supply of casuarina, jungle fuel and charcoal required for the use of this Division for the year 1918-19, published in Part IV, pages (144, 145 & 146) of the *Mysore Gazette* dated the 7th February 1918, tenders for which will be received by the undersigned up to 12 noon of 1st May 1918.

Abstract Notification.

The attention of the public is invited to the detailed Notification published in the issue of the 14th February 1918, calling for tenders for the supply of 730 tins of kerosene oil for the Harihar pumping station during the year 1918-19 which will be received by the undersigned up to 12 noon of the 1st May 1918.

S. SRINIVASA AIYAR,
Executive Engineer.